

% The Executive Engineer(E), BSNL Electrical Division First Floor, KTB TE Hanmakonda, Warangal					
No. (WO)/BSNL/ED/WGL/2022-23 / 208			Date:21 /03/2024.		
SPORT NOTICE INVITING QUOTATION					
No.07/NIQ/BSNL/ED/WGL/2023-24			Date 21-03-2024		
Executive Engineer (E), Bharat Sanchar Nigam Limited, Electrical Division, Warangal invites on behalf of the BSNL sealed spot quotations for the work as below from eligible contractors as per schedule attached. The quotations must be sealed and reach this office on the same day at <u>15:00 Hrs on 23-03-2024.</u>					
Name of work: - Providing Earthing and Lightning conductor works for RAN sites under Phase IX.2 4G Project for which Equipment allotted in Kareemnagar OA (Phase -III) SH :- KAA Bank Colony and KAA Pachchhunuru					
Sl. No.	Description of item	Qty	Rate	Unit	Amount
Schedule of work as per sheet attached					
The quotations will be opened on 23-03-2024 at 15:30Hrs					
Executive Engineer (E) BSNL Electrical Division Warangal					
<u>Copy to:-</u> 1) The S.E.(E),BSNL Electrical Zone , Hyderabad. 2) Notice board. . 3) The Sub Divisional Engineer (E) BSNL Elect. Sub Division-Warangal					
Enclosures to be provided by agency-					
1) Quotations complete including schedule.					

Name of work: Providing Earthing and Lightning conductor works for RAN sites under Phase IX.2 4G Project for which Equipment allotted in Kareemnagar OA (Phase -III) SH :- KAA Bank Colony and KAA Pachchhunuru

Sl.No	DESCRIPTION OF ITEM	Qty	Rate	Unit	Amount
Item 1	Earthing with GI earth plate 600x600x6 mm thick including accessories and providing masonry enclosure with cover plate having locking arrangement and watering pipe including charcoal and salt, etc., complete as required	2		Set	
Item 2	Providing and Fixing 25mmx5mm GI strip in 40mm dia medium class GI pipe from earth electrode etc. as required.	5		Mtr	
Item 3	Providing and fixing 25mm x 5mm GI strip on surface or in recess for connections etc. as required.	5		Mtr	
Item 4	Supplying and laying of 25 mm X 5 mm G.I strip at 0.50 metre below ground as strip earth electrode, including connection/terminating with G.I. nut, bolt, spring, washer etc. as required. (Jointing shall be done by overlapping and with 2 sets of G.I. nut bolt & spring washer spaced at 50mm) (For interconnection of existing earthings)	6		Mtr.	
Item 5	Improving of earth continuity from existing earth electrode upto to the earth bus/ earth terminations by making good of loose connections/joints including providing missing bolts/nuts,spring washers etc.,as required.	2		Job.	
Item 6	Providing 300mm x 50mm x 6 mm thick GI bus bar as main earth bus bar on wall surface on suitable insulators having suitable no. of holes for connections complete etc., as required.	2		Job.	
Item 7	Supplying and fixing lightning conductor finial made of 25 mm dia 1000 mm long GI hallow tube of minimum wall thickness of 1.6 mm fixed to the top of the tower with Teflon sleeve to avoid direct contact with tower etc., as required.	2		Each	

Total
 GST @18% _____
 Total including GST
 GRAND TOTAL
 Say

Executive Engineer(E)
 BSNL Electrical Division
 Warangal